

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-01378-00-00
Spot: NENENE Sec/Twnshp/Rge: 3-20S-2W
5139 feet from S Section Line, 278 feet from E Section Line
Lease Name: UNRUH, FRANK Well #: 1
County: MCPHERSON Total Vertical Depth: 2944 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2911		30 SX
SURF	8.625	155		100 SX

Well Type: SWD UIC Docket No: D05612.0 Date/Time to Plug: 06/12/2018 1:00 PM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Revd. from: ADRIAN MORALES Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: AS PER KCC RULES & REGS. USUALLY THIS CONSISTS OF A 50' SAND PLUG AT BOTTOM COVERED WITH A 5 SACK CEMENT PLUG. FILL FROM 250' TO SURFACE WITH CEMENT (ANNULUS AND CASING). CUT CASING OFF BELOW GROUND LEVEL. RESTORE GROUND AS NEEDED.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2018 1:00 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

Perfs:

PUMPED 60 SX COMMON CEMENT WITH 4% CALCIUM CHLORIDE DOWN TUBING. SET FOR 1 HOUR TAGGED WITH WIRELINE @ 2840'. PERFORATED @ 250'. TUBING STUCK, PULLED 1 JOINT AND PARTED @ 33'. RAN 1" DOWN BACKSIDE TO 200' REMOVED 1 JOINT TO 180' CIRCULATED 140 SX COMMON CEMENT WITH 4% CALCIUM CHLORIDE AND 150 LBS. OF COTTONSEED HULLS TO SURFACE.

Top	Bot	Thru	Comments
2840	2890	TBG	

INVOICED


JUL 17 2018

Remarks: COPELAND TICKET #46408 - FAILED MIT

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)