

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20907-00-01
Spot: NESWNW Sec/Twnshp/Rge: 29-26S-8E
3631 feet from S Section Line, 4464 feet from E Section Line
Lease Name: DRUMM Well #: 17
County: BUTLER Total Vertical Depth: 2764 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2637		
PROD	5.5	2763		75 SX
SURF	8.625	185		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2018 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: JIM SNYDER INC. Company: JIM SNYDER INC Phone: (620) 344-6283

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/23/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH WITH TUBING @ 2611', SNYDER MIXED & PUMPED 1/2 SX GEL & 5 BBLs FRESH WATER & 7 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 2160'. RIH W/DUMP BAILER & DUMP BAILED 7 SXS CLASS A COMMON. TAGGED CEMENT @ 2540'. RIH ON WIRELINE, CUT CASING @ 504', LAYED DOWN 504', 5.5" CASING. BAILED HOLE DRY @ 250', CMC, POURED 4 YARDS LY 2500 SLURRY MIX TO SURFACE. CEMENT CIRCUALTED. CMC TICKET #400049539 & 4015331.

Perfs:

Top	Bot	Thru	Comments
2693	2729	CSG	
2612	2621	CSG	


INVOICED
JUL 17 2018

Remarks: DENIED TA/ COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

1/5