

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-40684-00-00  
Spot: NENWSENW Sec/Twnshp/Rge: 27-34S-12E  
3749 feet from S Section Line, 3555 feet from E Section Line  
Lease Name: MCMILLAN Well #: 28  
County: CHAUTAUQUA Total Vertical Depth: 1200 feet

Operator License No.: 35368  
Op Name: JONES OIL EXPLORATION, LLC  
Address: PO BOX 68  
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD   | 7    | 1200       |             | 0 SX     |
| SURF   | 10   | 20         |             | 0 SX     |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2018 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: MATT JONES Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Cement is unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 05/03/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Fished rods and tubing out of well to 910'. Ran 1" to 910' gelled hole and spotted 20 sack plug. Pulled up to 800' and spotted 20 sack plug. Pulled 1" and perforated casing at 550' and 275'. Ran 1" back into 550' and spotted 20 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 172 sacks of cement with 3% gell were used to plug this well.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1140 | 1150 |      |          |

RECEIVED  
KCC DIST # 3  
JUN 06 2018  
CHANUTE, KS

DS  
INVOICED  
JUL 17 2018

Remarks: WELL WAS PLUGGED DUE TO AGREEMENT BETWEEN THE OPERATOR AND THE KCC.

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)