

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25832-00-00
Spot: SENESENW Sec/Twnshp/Rge: 35-16S-15W
1825 feet from N Section Line, 2315 feet from W Section Line
Lease Name: JAMES Well #: 1-35
County: BARTON Total Vertical Depth: 3680 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 183RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3654	2225	180 SX
SURF	8.625	865		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2018 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: SHELDON BENNETT Company: JASON OIL COMPANY, LLC DBA Phone: (785) 483-4204

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2018 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement. Cut casing at 2225'. Pulled casing to 1600' and pumped 125 sx cement w/300 # hulls. Pulled casing to 1150' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement. Pulled casing. Hole stayed full.

GPS: 38.61833 -098.95108

Perfs:

Top	Bot	Thru	Comments
3339	3343		
3329	3332		
3288	3292		
3276	3279		

INVOICED
JUL 17 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 521

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

MAY 03 2018

MAY 17 2018

RECEIVED

Form CP-2/3