

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21177-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 26-8S-19W
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: VEVERKA Well #: 7
County: ROOKS Total Vertical Depth: 3368 feet

Operator License No.: 34903
Op Name: JASPAR CO.
Address: PO BOX 1120
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3362		150 SX
SURF	8.625	167		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2018 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: SHANE VEHIGE Company: JASPAR CO. DBA Phone: (785) 650-4910

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3012' - 3350'.
DV Tool set at 1334' w/375 sx cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2018 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3290' and pumped 50 sx cement w/300 # hulls. Pulled tubing to 2808' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1843' and pumped 100 sx cement. Pulled tubing to 842' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Pressured with 300#. Shut in pressure 200#.

GPS: 39.33345N -099.41719W

Perfs:

Top	Bot	Thru	Comments
3346	3350		
3294			
3290			
3270			
3254			
3142			
3105	3108		
3088	3090		
3012	3016		

INVOICED
JUL 17 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 827

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 12 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAY 22 2018