

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-20253-00-00

Spot: NESWSW

Sec/Twnshp/Rge: 35-33S-2E

990 feet from S Section Line,

4290 feet from E Section Line

Lease Name: CASTER

Well #: 7

County: SUMNER

Total Vertical Depth: 2800 feet

Operator License No.: 32984

Op Name: GOBY ENERGY, INC.

Address: 51000 TWO RIVERS PLAZA  
GLENWOOD SPRINGS, CO 81601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2799	1510	100 SX
SURF	8.625	249		250 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/10/2018 8:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Revd. from: STEVE BECKLEY

Company: GOBY ENERGY INC.

Phone: (970) 618-7127

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/17/2018 10:00 AM

KCC Agent: DAN FOX

**Actual Plugging Report:**

**Perfs:**

CIBP SET AT 2650' RAN IN WITH BAILER AND DUMPED 2 SX OF COMMON ON TOP OF PLUG, SHOT OFF CASING AT 1510', PULLED CASING UP TO 320' PUMPED 140 SX OF CEMENT AND CIRCUALTE UP THE BACK SIDE OF 8 5/8". PULLED THE REST OF THE PRODUCTION CASING OUT OF HOLE. RETURNED TO CHECK TOP PLUG WHICH HAD FALLEN ABOUT 20' AND OPERATOR TOPPED OFF. CUT OFF CASING BELOW GROUND. PLUG JOB COMPLETE.

Top	Bot	Thru	Comments
2698	2706	CSG	


INVOICED  
JUL 17 2018

Remarks: NOTE: OPERATOR PLUGGED WELL DUE TO A NOV LETTER RECEIVED FROM DIST 2 STAFF.  
COMPLIANCE MET BEFORE AN ORDER WAS ISSUED.

Plugged through: CSG

District: 02

Signed

  
(TECHNICIAN)