

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04669-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 3-17S-12W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STUMPS Well #: 1
County: BARTON Total Vertical Depth: 3332 feet

Operator License No.: 30163
Op Name: GREAT PLAINS PETROLEUM, INC.
Address: 221 CIRCLE DR
WICHITA, KS 67218

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3328		75 SX
SURF	8.625	276		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2018 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROD PHARES Company: GREAT PLAINS PETROLEUM, INC. Phone: (316) 685-8800

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Tried to retrieve packer from 3221'. Packer stuck in casing at 620'. Tried to push packer back down well and it would not move up or down. Tried to turn packer and it would start to tighten up and then spin. Did not want to mill on the packer and risk closing off opening through the packer to perforate the salt section and Anhydrite. Will plug from there.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Set down on packer with 2 7/8" tubing. Ran down through packer with slim perf gun to perforate at 1400' and 750'. Chained tubing down to wellhead and pumped 300 sx cement w/500 # hulls. Had circulation on backside and casing. Shut in casing to pump cement down below packer and backside went on a vacuum. Pulled tubing. Ran in and perforated at 200'. Shut down for the day.
04/13/2018 - Ran tubing in and tagged cement at 600'. Tied to tubing. Circulated cement to surface on casing and surface pipe with 150 sx cement.

GPS: 38.60427 -098.63624

INVOICED

JUL 17 2018

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

MAY 01 2018

MAY 17 2018

Form CP-2/3

RECEIVED