

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23884-00-00
Spot: SESENE Sec/Twnshp/Rge: 22-15S-17W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: ROTH Well #: 1
County: ELLIS Total Vertical Depth: 3573 feet

Operator License No.: 33864
Op Name: HABIT PETROLEUM, LLC
Address: 639 280TH AVE PO BOX 243
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3573		125 SX
SURF	8.625	211		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2018 9:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: IRVIN E HASELHORSST Company: HABIT PETROLEUM, LLC DBA Phone: (785) 623-1154

Proposed Plugging Method: No Alt II records.
Ordered 250 sx 60/40 pozmix 4% gel cement w/800 # gel and 200 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2018 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1700', 1100', 500' and 220'. Ran tubing to 3000'. Global Cementing pumped 7 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1700' and pumped 100 sx cement w/100 # hulls. Cement circulated. PTOH. Topped 4 1/2" casing off with 25 sx cement. Hooked up to backside and pumped 40 sx cement.

Perfs:

Top	Bot	Thru	Comments
3573	3575		
3468	3470		
3369	3371		
3296	3298		

INVOICED
JUL 17 2018

Remarks: GLOBAL CEMENTING TICKET # 3279

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3