

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23989-00-00
Spot: E2SENWSW Sec/Twnshp/Rge: 23-15S-17W
1650 feet from S Section Line, 1290 feet from W Section Line
Lease Name: TIEDEMANN Well #: 3
County: ELLIS Total Vertical Depth: 3558 feet

Operator License No.: 33864
Op Name: HABIT PETROLEUM, LLC
Address: 639 280TH AVE PO BOX 243
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3558		125 SX
SURF	8.625	215		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2018 2:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: IRVIN E HASELHORST Company: HABIT PETROLEUM, LLC DBA Phone: (785) 623-1154

Proposed Plugging Method: No Alt II records.
Ordered 275 sx 60/40 pozmix 4% gel cement w/700 # gel and 300 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2018 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1700', 1100' and 500'. Ran tubing to 3000'. Global Cementing pumped 7 sx gel followed by 75 sx cement w/150 # hulls. Pulled tubing to 1700' and pumped 115 sx cement w/150 # hulls. Pulled tubing to 500' and pumped 25 sx cement. Cement circulated. PTOH. Topped off 4 1/2" casing with 10 sx cement. Casing is full. Hooked up to backside with instant pressure of 500#.

Perfs:

Top	Bot	Thru	Comments
3404	3406		
3348	3352		
2968	2972		
1949	3555		

INVOICED
JUL 17 2018

Remarks: GLOBAL CEMENTING ticket # 3280

Plugged through: TBG

District: 04

Signed Richard Williams

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

JUN 05 2018