

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25357-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 1-18S-15W
1442 feet from S Section Line, 4068 feet from E Section Line
Lease Name: HILDRETH Well #: 3
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3625	2000	150 SX
SURF	8.625	1020		375 SX

Well Type: EOR UIC Docket No: E30541.1 Date/Time to Plug: 05/14/2018 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 05/11/2018 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 2006'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1000' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement.

GPS: 38.51094 -098.93668

Perfs:

Top	Bot	Thru	Comments
3564	3568		
3472	3476		
3453	3457		
3439	3443		

INVOICED
JUL 17 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 12 2018

CONSERVATION DIVISION
WICHITA, KS

MAY 22 2018

Form CP-2/3