

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21690-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 16-32S-12E
1699 feet from S Section Line, 589 feet from E Section Line
Lease Name: STICH/HARTWICK Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 1220 feet

Operator License No.: 35261
Op Name: OAST, THOMAS H.
Address: 524 N. SCHOOL
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1215		140 SX
SURF	7	60		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2018 12:00 AM
Plug Co. License No.: 35463 Plug Co. Name: SWS OPERATIONS LLC
Proposal Rcvd. from: THOMAS H. OAST Company: _____ Phone: (918) 440-6512

Proposed Plugging Method: Plug in accordance with KCC rules and regulations.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 05/29/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" hose off of spool to 1130' gelled hole and spotted 5 sack plug. Pulled up to 750' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 44 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1135	1166		

RECEIVED
KCC DIST #3
JUN 06 2018
CHANUTE, KS


DS

INVOICED
JUL 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)