

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21261-00-00
Spot: SEWNENW Sec/Twnshp/Rge: 29-33S-29W
4638 feet from S Section Line, 3326 feet from E Section Line
Lease Name: SINGLEY WEST Well #: 2-29
County: MEADE Total Vertical Depth: 6277 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>32211</u>	CIBP		5960		WITH 2 SX CMT
Op Name: <u>O'BRIEN ENERGY RESOURCES CORP.</u>	PROD	4.5	6277	2600	WITH 220 SX CMT
Address: <u>18 CONGRESS ST, STE 207</u> <u>PORTSMOUTH, NH 03801</u>	SURF	8.625	1530		WITH 785 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/31/2018 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RON KERR Company: KERR WELL SERVICE Phone: (620) 629-0400

Proposed Plugging Method: SET CIBP @ 5960' WITH 2 SX CMT. SET CIBP @ 5760' WITH 2 SX CMT. PLUG AT 1580' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2018 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5960' WITH 2 SX CMT. SET CIBP @ 5760' WITH 2 SX CMT. PRESSURED CASING TO 600 PSI. LOADED HOLE WITH MUD. 1ST PLUG AT 1580' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6093	6100		
6021	6027		

INVOICED
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Larry Harris
(TECHNICIAN)

RECEIVED
JUN 11 2018
KCC DODGE CITY