

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21275-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 29-33S-29W
4475 feet from S Section Line, 4413 feet from E Section Line
Lease Name: SINGLEY WEST Well #: 3-29
County: MEADE Total Vertical Depth: 6320 feet

Operator License No.: 32211
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5760		WITH 2 SX CMT
CIBP		5856		WITH 2 SX CMT
PROD	4.5	6292	2714	WITH 225 SX CMT
SURF	8.625	1486		WITH 775 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2018 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: PAUL WIEMAN Company: O'BRIEN ENERGY RESOURCES Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5856' WITH 2 SX CMT. SET CIBP @ 5760' WITH 2 SX CMT. LOAD HOLE. PRESSURE TEST CASING. PLUG AT 1535' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2018 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

CIBP @ 5856' WITH 2 SX CMT. CIBP @ 5760' WITH 2 SX CMT. LOAD HOLE WITH MUD. PRESSURE TO 600 PSI. 1ST PLUG AT 1535' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5876	5884		
5830	5836		
5808	5824		

INVOICED
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUN - 5 2018
KCC DODGE CITY