

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-119-21306-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 29-33S-29W  
1984 feet from S Section Line, 3011 feet from E Section Line  
Lease Name: SINGLEY WEST Well #: 4-29  
County: MEADE Total Vertical Depth: 6404 feet

Operator License No.: 32211  
Op Name: O'BRIEN ENERGY RESOURCES CORP.  
Address: 18 CONGRESS ST, STE 207  
PORTSMOUTH, NH 03801

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 5727       |             | WITH 2 SX CMT   |
| CIBP   |       | 6180       |             | WITH 2 SX CMT   |
| PROD   | 4.5   | 6382       | 2212        | WITH 235 SX CMT |
| SURF   | 8.625 | 1510       |             | WITH 550 SX CMT |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/29/2018 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: PAUL WIEMAN Company: O'BRIEN ENERGY Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5727' WITH 2 SX CMT. SET CIBP @ 5180' WITH 2 SX CMT. LOAD HOLE. PRESSURE TEST CASING. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40'. CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/29/2018 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5727' WITH 2 SX CMT. SET CIBP @ 6180' WITH 2 SX CMT. PRESSURED UP CASING TO 600 PSI. LOAD HOLE WITH HEAVY MUD. 1ST PLUG AT 1561' WITH 50 SX CMT. 2ND PLUG AT 590' WITH 50 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 40 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 6259 | 6269 |      |          |
| 6233 | 6239 |      |          |
| 5777 | 5806 |      |          |

INVOICED:  
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Larry Harris  
(TECHNICIAN)

RECEIVED  
JUN - 5 2018  
KCC DODGE CITY