

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21317-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 5-34S-28W
2035 feet from S Section Line, 3238 feet from E Section Line
Lease Name: VANDERPOOL Well #: 1-5
County: MEADE Total Vertical Depth: 6405 feet

Operator License No.: 32211
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5635		WITH 2 SX CMT
PROD	4.5	6287	2714	WITH 220 SX CMT
SURF	8.625	1485		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2018 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RON KERR Company: KERR WELL SERVICE Phone: (620) 629-0400

Proposed Plugging Method: CIBP @ 5635' WITH 2 SX CMT. PLUG AT 1535' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2018 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5635' WITH 2 SX CMT. PRESSURED CASING TO 600 PSI. LOAD HOLE WITH MUD. 1ST PLUG AT 1545' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5686	5689		

INVOICED
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUN - 8 2018
KCC DODGE CITY