

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-131-20105-00-00
Spot: SWSENE Sec/Twnshp/Rge: 23-5S-12E
3008 feet from S Section Line, 1008 feet from E Section Line
Lease Name: GROSSNICKLE Well #: 5
County: NEMAHA Total Vertical Depth: 2751 feet

Operator License No.: 31424
Op Name: NORTH PLAINS CORP.
Address: 8801 S YALE STE 240
TULSA, OK 74137

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 2746 | | 175 SX |
| SURF | 8.625 | 278 | | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2018 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Revd. from: WAYNE BECK Company: _____ Phone: (785) 547-5208

Proposed Plugging Method: Fill 5-1/2" csg w/ gel mud from TD @ 2751' to approx. 2550'. Cover Viola perms w/ 50' plug (approx. 20 sx) 60/40 POZ w/ 4% gel. Set 50' plug (approx. 20 sx) opposite Kansas City Fm. @ 1300'. Set cmt plug from 350' surface w/ approx. 120 sx.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 04/16/2018 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

CLEAN TUBING AND EQUIPMENT OUT OF HOLE THEN SHOOT PERFS IN 5-1/2 INCH CASING AT 1300 AND 310 FEET WITH 2 SHOTS PER FOOT. RUN 89 JOINTS OF 2-7/8 INCH TUBING INTO HOLE THEN ESTABLISH CIRCULATION TO CLEAN OUT HOLE. PUMP APPROXIMATELY 180 FEET OF CEMENT ACROSS VIOLA (PRODUCING ZONE) PERFS. PULL TUBING TO APPROXIMATELY 1300 FEET AND PUMP APPROXIMATELY 90 FEET OF CEMENT. PULL TUBING TO APPROXIMATELY 310 FEET AND PUMP CEMENT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2498 | 2504 | | |
| 2480 | 2490 | | |

RECEIVED
KCC DIST # 3
JUN 13 2018
CHANUTE, KS

INVOICED
JUL 17 2018

LS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)