

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21571-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 1-24S-10W
2287 feet from N Section Line, 880 feet from E Section Line
Lease Name: PHYLLIS Well #: B-1
County: RENO Total Vertical Depth: 4128 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4128		250 SX
SURF	8.625	211		340 SX
T1	2.375	3693		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2018 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: KIRK GLENN Company: _____ Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3650' + 2 SK CEMENT ON TOP, AND PERFORATED @ 1450'-950' & 260', SPOTTED 12 SACKS GEL AND 50 SACKS COMMON CEMENT WITH 4% CC AT 1450'. TAGGED PLUG @ 1020'. SPOTTED 35 SACKS COMMON CEMENT WITH 4% CC @ 950'. @ 260' CIRCULATED TO SURFACE WITH 115 SACKS OF 60-40 POZ MIX. 3/6/18 CUT HEAD OFF AND TOPPED OF CASING WITH 18 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3703	3739		

SCANNED

INVOICED
JUL 17 2018

Remarks: COPELAND CEMENTING - GREAT BEND - TICKET #47601 - DENIED TA NIO LEASE

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)