

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21310-00-01
Spot: SENENW Sec/Twnshp/Rge: 12-24S-10W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BEVERLY Well #: 1
County: RENO Total Vertical Depth: 4131 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		
PKR		3929		
PROD	5.5	4131		205 SX
SURF	8.625	247		0 SX
T1	2.375	4032		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2018 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: KIRK GLENN Company: _____ Phone: (620) 282-2212

Proposed Plugging Method: KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2018 4:00 PM KCC Agent: B. J. HOPE


Actual Plugging Report:

SET CIBP @ 3900' 2 SX CEMENT ON TOP, AND PERFORATED @ 1450'-900' & 300'. SPOTTED 12 SACKS GEL AND 60 SACKS COMMON CEMENT WITH 3% CC AT 1450'. TAGGED PLUG @ 1020'. SPOTTED 35 SACKS COMMON CEMENT WITH 3% CC @ 900'. TAGGED PLUG @ 761' @ 300' CIRCULATED TO SURFACE WITH 115 SACKS OF 60/40 POZ MIX. 3/9/18 CUT HEAD OFF AND TOPPED OFF CASING WITH 12 SX OF CEMENT.

INVOICED
JUL 17 2018

Perfs:

Top	Bot	Thru	Comments
3726	3739		



Remarks: COPELAND CEMENTING - GREAT BEND - TICKET #47601 - DENIED TA NO LEASE

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)