

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26767-00-00  
Spot: SWNESWNW Sec/Twnshp/Rge: 35-13S-19W  
1795 feet from N Section Line, 956 feet from W Section Line  
Lease Name: YOUNGER Well #: 1  
County: ELLIS Total Vertical Depth: 3925 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3924		320 SX
SURF	8.625	209		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2018 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY DBA Phone: (620) 241-4640

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.  
DV tool at 1434' w/170 sx cement.  
Perforations: 3557' - 3626' LKC  
Arb: 3850' - 3857'. CIBP set at 3780'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/09/2018 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3552'. Quality rigged to tubing and pumped 10 sx gel followed by 75 sx cement w/300 # hulls mixed in. Pulled tubing to 2050' and pumped 160 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 25 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 15 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.88042 -099.40707

Perfs:

Top	Bot	Thru	Comments
3850	3857		
3622	3626		
3580	3584		
3557	3564		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 02 2018**  
CONSERVATION DIVISION  
WICHITA, KS


INVOICED  
AUG 02 2018

Remarks: QUALITY OIL WELL CEMENTING TICKET # 799

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 02 2018**

CONSERVATION DIVISION  
WICHITA, KS

AUG 15 2018