

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22948-00-00
Spot: S2NENESE Sec/Twnshp/Rge: 18-8S-22W
2140 feet from S Section Line, 330 feet from E Section Line
Lease Name: QUINT G Well #: 1-18
County: GRAHAM Total Vertical Depth: 3632 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3687		125 SX
SURF	8.625	218		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2018 10:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. DBA Phone: (785) 445-6270

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
Port Collar at 1812' w/225 sx cement.
Perforations: 3442' - 3446', 3510' - 3512', 3517' - 3520' and 3533' - 3536'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2018 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' and pumped 11 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1775' and pumped 175 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.35612 -099.80988

Perfs:

Top	Bot	Thru	Comments
3533	3536		
3517	3520		
3510	3512		
3442	3446		

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS


INVOICED
AUG 02 2018

Remarks: QUALITY CEMENT TICKET # 868

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

JUL 16 2018

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3