

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21068-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 12-6S-20W
3300 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HANSEN FOUNDATION Well #: 1
County: ROOKS Total Vertical Depth: 4496 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3611		150 SX
SURF	8.625	285		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2018 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Production perforations: 3363' - 3530'.
Packer stuck in hole at 3319', TOF 3288'.
Squeeze jobs: 1347' - 1379' w/100 sx cement and 2918' - 2948' w/125 sx cement.
Ordered 325 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2018 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3263'. Swift Services pumped 75 sx cement w/300 # hulls. Pulled tubing to 2730' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 1164' and pumped 100 sx cement. Cement circulated. Pulled tubing. Topped off 4 1/2" casing with 25 sx cement. Hooked up to backside and pumped 50 sx cement. Maximum pressure 125#.

GPS: 39.36074 -099.14993

Perfs:

Top	Bot	Thru	Comments
3524	3530		
3491	3494		
3444	3447		
3437	3439		
3400	3404		
3363	3367		

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

INVOICED
AUG 02 2018

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

CM

JUL 16 2018

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3