

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24497-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 11-16S-14W  
1650 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: KARST A Well #: 2  
County: BARTON Total Vertical Depth: 3374 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3340		175 SX
SURF	8.625	434		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2018 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 14 sx gel and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/16/2018 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 880' and 400'. Ran tubing to 3330' and pumped 14 sx gel folowed by 50 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 875'. Circulated cement to surface on casing and surface pipe with 100 sx cement. Pulled tubing. Topped off with 25 sx cement.

GPS: 38.67116 -098.84625

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
**AUG 02 2018**  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
AUG 02 2018

Remarks: HURRICANE SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

JUL 17 2018

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3