

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20926-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 6-10S-24W
440 feet from N Section Line, 440 feet from W Section Line
Lease Name: RIEDEL Well #: 4
County: GRAHAM Total Vertical Depth: 4104 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4099		275 SX
SURF	8.625	191		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2018 2:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 3823' - 3828', 3942' - 3947'.
Rods parted at 3789'.
Tubing parted at 3228'.
Tried to fish rods and tubing. Could not recover more.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2018 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2900', 2160', 1285' and 185'. Ran tubing to 3195' and pumped 100 sx cement. Pulled tubing to 2257' and pumped 280 sx cement w/400 # hulls. Good circulation of cement. Pulled tubing out. Casing is full. Topped off with 10 sx cement. Tied on to backside and squeezed with 60 sx cement. Shut in pressure 90 psi.

GPS: 39.21773 -100.05028

Perfs:

Top	Bot	Thru	Comments
3998	4003		
3975	3980		
3952	3958		
3851	3860		

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS


INVOICED
AUG 02 2018

Remarks: HURRICANE CEMENT TICKET # 1184

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 24 2018

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS