

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-20880-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 14-5S-31W  
2310 feet from S Section Line, 660 feet from E Section Line  
Lease Name: SHERILYN Well #: 1-14  
County: RAWLINS Total Vertical Depth: 4465 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4458		175 SX
SURF	8.625	219		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2018 8:30 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/1000# gel and 500 # hulls.  
8 5/8" surface casing set at 219' w/175 sx cement.  
5 1/2" production casing set at 4458' w/175 sx cement. TOC 3120'.  
TD 4465'. PBT 4420'.  
Port Collar set at 2630' w/200 sx cement.  
Perforations: 4021' - 4028', 4321' - 4328'. CIBP set at 4370'. Perforations below plug: 4382' - 4394'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/29/2018 12:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4000' and pumped 1000# gel followed by 65 sx cement w/300 # hulls. Pulled tubing to 2660' and pumped 130 sx cement w/50 # hulls. Pulled tubing to 1330' and pumped 145 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement. Pressured to 300 psi.

GPS: 39.61825N -100.76185W

Perfs:

Top	Bot	Thru	Comments
4382	4394		CHEROKEE
4321	4328		
4021	4028		LKC 'F'

Received  
KANSAS CORPORATION COMMISSION  
**AUG 02 2018**  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
AUG 02 2018

Remarks: HURRICANE SERVICES PULLING UNIT AND CEMENT SERVICES TICKET # 1137

Plugged through: TBG

District: 04

Signed Darrel Dipman  
KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

~~JUN 29 2018~~

AUG 02 2018  
CONSERVATION DIVISION  
WICHITA, KS