

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22344-00-00
Spot: S2NENE Sec/Twnshp/Rge: 5-7S-20W
990 feet from N Section Line, 660 feet from E Section Line
Lease Name: LESAGE B Well #: 3
County: ROOKS Total Vertical Depth: 3730 feet

Operator License No.: 34903
Op Name: JASPAR CO.
Address: PO BOX 1120
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3725		150 SX
SURF	8.625	260		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2018 1:30 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: SHANE VEHIGE Company: JASPAR CO. DBA Phone: (785) 650-4910

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Production perforations: 3435' - 3437', 3688' - 3696' and 3725' - 3730' OH.
1600' w/350 sx cement.
Casing leak at 2700' - 2710'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2018 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3369' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 2484' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 1279' and pumped 80 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing with 20 sx cement. Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.

GPS: 39.47840N -099.56789W

Perfs:

Top	Bot	Thru	Comments
3688	3696		
3629	3631		
3611	3613		
3598	3600		
3580	3582		
3528	3530		
3485	3487		
3435	3437		

INVOICED
AUG 02 2018

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING TICKET # 866

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

JUL 16 2018

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3