

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22239-00-00  
Spot: NENENE Sec/Twnshp/Rge: 5-7S-20W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: LESAGE B Well #: 1  
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 34903  
Op Name: JASPAR CO.  
Address: PO BOX 1120  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3699		150 SX
SURF	8.625	260		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2018 8:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: SHANE VEHIGE Company: JASPAR CO. DBA Phone: (785) 650-4910

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Production perforations: 3415' - 3418', 3665' - 3669' and 3618' - 3700' OH.  
Casing leak at 1400' - 1420'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2018 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1800' and 1150'. Ran tubing to 3355' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 2496' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 1295' and pumped 80 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing with 20 sx cement. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.

GPS: 39.48012N -099.56676W

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
**AUG 02 2018**  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
AUG 02 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 865

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

JUL 16 2018

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3