

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-21043-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 10-1S-33W
335 feet from N Section Line, 420 feet from E Section Line
Lease Name: HORINEK Well #: 1-10
County: RAWLINS Total Vertical Depth: 4183 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4173 | | 200 SX |
| SURF | 8.625 | 221 | | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2018 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO INC D Phone: (785) 621-2610

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 6 sx gel (100 # bags) and 500 # hulls.
Production perforations: 3792' - 4116'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2018 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3876' and pumped 6 sx gel, 75 sx cement and 400 # hulls. Pulled tubing to 2884' and pumped 90 sx cement. Pulled tubing to 1934' and pumped 90 sx cement. Pulled tubing to 950' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 5 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 50 sx cement at 100 psi.

GPS: 39.98679N -101.00154W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4113 | 4116 | | |
| 4055 | 4059 | | |
| 4013 | 4018 | | |
| 3955 | 3958 | | |
| 3804 | 3806 | | |
| 3792 | 3796 | | |

Received
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

INVOICED

AUG 02 2018

Remarks: GLOBAL CEMENTING TICKET # 3390

Plugged through: TBG

District: 04

Signed Pat Bedore
RECEIVED KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

JUL 16 2018

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS