

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22632-00-00
Spot: NENENWSW Sec/Twnshp/Rge: 20-14S-22W
2460 feet from S Section Line, 1215 feet from W Section Line
Lease Name: HELLER -SCHOENTHALER Well #: 1-20
County: TREGO Total Vertical Depth: 4265 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4265		155 SX
SURF	8.625	212		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2018 9:00 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO INC D Phone: (785) 621-2610

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 17 sx gel and 400 # hulls.
Port Collar set at 1632' w/150 sx cement.
CIBP set at 4156' and 4102'.
Perforations: 4003' - 4018', 4132' - 4136', 4140' - 4143' and 4170' - 4174'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2018 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3956' and pumped 17 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1700' and pumped 175 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
4170	4174		
4140	4143		
4132	4136		
4003	4018		

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

INVOICED
AUG 02 2018

Remarks: SWIFT CEMENT TICKET # 31600

Plugged through: TBG

District: 04

Signed

RECEIVED
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 29 2018

AUG 02 2018

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS