

6 060188

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE, SEC. 3, T. 20 S, R. 11 W
2310 feet from WS section line
330 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339
Operator: Bergman Oil Co.
Name & Address: 520 Union Center
Wichita, Ks. 67202

Lease Name Penning Well # 4
County Barton
Well Total Depth 3292 106.99 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 11:30 AM Day: 30 Month: March Year: 19 84

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs 50 foam mix - 6% Gel - 3% Gel. U., 19 lbs. Gel, 5 lbs. balls
& 8 5/8" plug.

Plugging Proposal Received by Ruth G. Schul
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 30 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - C. 250' w/cuc. 5 1/2" set at 3291' w/150 lbs.
13' of open hole. Plug bottom w/ 5 lbs. cement, sand & 5 lbs. cement to
3250'. Set pipe 7 times & recovered 1700'. Pumped in 8 5/8" - 4 lbs. balls,
25 lbs. cement, 12 lbs. Gel, 40 lbs. cement, 3 lbs. Gel, 1 lb. balls, released plug
& followed w/ 100 lbs. cement w/ 400 pounds pressure

Remarks: By Sun Cementing
(If additional description is necessary, use BACK of this form.)
I (did or did not) observe this plugging.

Signed Ruth G. Schul
(TECHNICIAN)

INVOICED

DATE 4-11-84

INV. NO. 1111
3-30

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1984
4-10-84
CONSERVATION DIVISION
Wichita, Kansas