

6 060517

15.009.14319 .0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW, SEC. 3, T. 20 S, R. 11 W

4290 feet from S section line

4950 feet from E section line

Lease Name Panning Dish Well # 5County Corton 107.67Well Total Depth 3313 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 160 ✓

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339Operator: Bergman Oil Co.Name & Address 520 Union Center,Wichita, Mo.67202Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050Address Box 176, Chase, Mo. 67524Company to plug at: Hour: 10:00 AM Day: 28 Month: March Year: 19 85Plugging proposal received from Clay Dantg(company name) Kelso Casing Pulling (phone) 316-938-2457were: Order 165 sh. 30 permix - 6 7/8 Gel - 3 7/8 Gel, 15 sh. Gel, 5 sh. hulls &8 5/8 plug.Plugging Proposal Received by Arthur E. Loh

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 11:00 AM Day: 28 Month: March Year: 19 85ACTUAL PLUGGING REPORT 8 5/8" - 160' w/ 200 sh. 5 1/2" at 3312' w/ 100 sh.1' of open hole. Plugged bottom w/ 5 sh. cement, sand & 5 sh. cement to3260'. Shot pipe 1 time & recovered 2200'. Pumped in 8 5/8" 4 sh. hulls,25 sh. cement, 12 sh. Gel, 40 sh. cement, 3 sh. Gel, 1 sh. hulls, released plug& followed w/ 100 sh. cement w/ 500 pounds pressure.RECEIVED
STATE CORPORATION COMMISSION
APR 05 1985 4-5-85Remarks: By Buie Cementing Co.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-8-85Signed Arthur E. Loh

(TECHNICIAN)

INV. NO. 7613 3-28