

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21544-00-00  
Spot: E2W2SWSW Sec/Twnshp/Rge: 30-26S-10W  
660 feet from S Section Line, 560 feet from W Section Line  
Lease Name: BRANSCOM Well #: 1  
County: RENO Total Vertical Depth: 4400 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 125 N MARKET ST STE 1110  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4396	1730	125 SX
SURF	8.625	264		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2018 12:00 AM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: TODD ALLAM Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/15/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

WELL HAD 1175 LBS OF PRESSURE ON IT. ATTACHED KILL TRUCK AND PUMPED 120 BBLs OF HEAVY WATER TO KILL WELL. ATTACHED FULL OPEN WORKING VALVE TO CASING, TO WORK THROUGH. SET CIBP (8k) @ 4230' CAPPED WITH 10 SX CEMENT ON TOP WITH 3% GAS BLOCK. PRESSURE TESTED CASING TO 500 LBS, HELD. CUT CASING PIPE OFF @ 1748', PULLED CASING TO 1533', PUMPED 1700 LBS OF GEL, SPOTTED 50 SX CEMENT. WAITED 2 HOURS - TAGGED @ 1480'. PULLED CASING TO 890' SPOTTED 35 SX CEMENT. PULLED CASING TO 308' CIRCULATED TO SURFACE WITH 125 SX CEMENT. TAGGED TOP OF CEMENT 105' DOWN - 5/16/18 TOPPED WITH 40 SX CEMENT, HAD TO GO ONE INCH DOWN INSIDE SURFACE CASING BECAUSE FLUID FROM PIT GOT BACK DOWN CASING.

Perfs:

Top	Bot	Thru	Comments
4278	4284		

INVOICED  
JUL 25 2018

Remarks: BASIC ENERGY PROVIDED CEMENT - ALL CLASS A 3% CC & 3% GAS BLOCK - TICKET #16643. NO LEASE.

Plugged through: CSG

District: 02

Signed B. J. Hope  
(TECHNICIAN)