

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21545-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 31-26S-10W
350 feet from N Section Line, 2290 feet from E Section Line
Lease Name: KERSCHEN TRUST Well #: V1-31
County: RENO Total Vertical Depth: 4375 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4213	1748	100 SX
SURF	8.625	241		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2018 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Revd. from: TODD ALLAM Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/15/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4000' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1748'. PULLED CASING TO 1533' AND PUMPED 1700 LBS OF GEL SPOTTED 50 SX CEMENT. WAITED 2 HOURS - TAGGED @ 1475'. PULLED CASING TO 930' SPOTTED 35 SX CEMENT. PULLED CASING TO 300' CIRCULATED TO SURFACE WITH 150 SX CEMENT. TAGGED TOP OF CEMENT 120' DOWN - 5-15-18 TOPPED WITH 50 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4048	4061		

INVOICED
JUL 25 2018

Remarks: BASIC ENERGY PROVIDED CEMENT - ALL CLASS A 3% CC - TICKET #16482.. WAS A TA'D WELL.

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)