

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-02805-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-23S-4W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: TETEN J H Well #: 2
County: RENO Total Vertical Depth: 3430 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	12.5	306		
LI	4.5	3251	610	
PROD	6.625	3430		250 SX
SURF	10.75	491		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JASON A. GEHRMANN Company: KAHAN & ASSOCIATES Phone: (918) 492-9797

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/03/2018 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

7-2-18 A CIBP WAS SET AT 3232' & CAPPED WITH 2 SKS CEMENT. CUT & PULLED 4 1/2" LINER FROM 610'. RAN IN HOLE WITH WIRELINE & SHOT 4 HOLES IN 6 5/8" CASING AT 603'. RAN TUBING TO 600' & PUMPED 150# HULLS, 6 SKS GEL & 100 SX COMMON CEMENT 3% CACL. LET SET OVER NITE. 7-3-18 TAGGED CEMENT INSIDE 6 5/8" AT 225'. RAN IN HOLE & PERFORATED 6 5/8" @ 219'-222'. WELDED COLLAR ON 6 5/8" & TIED ONTO CASING & PRESSURED UP TO 1000 #S. RAN 1" PIPE TO 210' & CIRCUALTED CEMENT TO SURFACE WITH 30 SKS CEMENT. BACKSIDE OF 6 5/8" CEMENTED PRIOR TO PLUG JOB.

Perfs:

Top	Bot	Thru	Comments
3352	3360		
3338	3342		

INVOICED
JUL 25 2018

Remarks: COPELAND ACID & CEMENT. COMMON CEMENT 3% CACL. DENIED TA

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)