

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-127-20480-00-00  
Spot: N2NENESE Sec/Twnshp/Rge: 15-16S-5E  
2460 feet from S Section Line, 333 feet from E Section Line  
Lease Name: BUTLER Well #: A-2  
County: MORRIS Total Vertical Depth: 2240 feet

Operator License No.: 35269

Op Name: CK OIL & GAS LLC

Address: 906 E. TRAPP ST.  
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2238		75 SX
SURF	8.625	250		178 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/26/2018 12:00 AM

Plug Co. License No.: 35269

Plug Co. Name: CK OIL & GAS LLC

Proposal Rcvd. from: CHRIS KREMEIER

Company: CK OIL & GAS

Phone: (785) 307-5701

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/03/2018 11:30 AM

KCC Agent: JERRY SPARLING

Actual Plugging Report:

Perfs:

JUNE 27, 2018 RIG RAN IN AND TAGGED BOTTOM @ 2250'. DROPPED SAND AND 5 SX COMMON CEMENT WITH BAILER. TAGGED @ 2130', SECOND PLUG @ 1140'.  
JUNE 28, 2018 PERFORATED @ 250'. JULY 3, 2018 QUALITY WELL SERVICE PUMPED 850' GEL SPACER (4 SX) TO 250' THROUGH 2 3/8" TUBING. QUALITY WELL SERVICE PUMPED 40 SX COMMON CEMENT THROUGH 2 3/8" TUBING FROM 240' AND CIRCUALTED TO SURFACE. TIED ONTO BACKSIDE AND PUMPED 10 SX TO SURFACE.

Top	Bot	Thru	Comments
2202	2212	CSG	
2182	2195	CSG	

INVOICED

JUL 25 2018

Remarks: QUALITY WELL SERVICE TICKET # 6874 50 SX. CEMENT 4 SX GEL.

Plugged through: CSG

District: 02

Signed

  
(TECHNICIAN)