

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-20185-00-00
Spot: SWNE Sec/Twnshp/Rge: 8-21S-1W
4088 feet from S Section Line, 699 feet from E Section Line
Lease Name: ED SCHROEDER Well #: 1
County: MCPHERSON Total Vertical Depth: 3010 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	4.5	2970		
PROD	5.5	3010		75 SX
SURF	8.625	160		120 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/15/2018 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: ANDREW RHEA Company: LOWEN OPERATOR Phone: (620) 654-6976

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/03/2018 11:30 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RIG RAN IN AND TAGGED BOTTOM @ 2970'. SANDED OFF BOTTOM TO 2900' AND TOPPED WITH 4 SXS COMMON CEMENT. GEMINI WIRELINE PERFORATED @ 250' WITH 4 SHOTS QES RIGGED UP AND PUMPED 75 SX OF 60/40 POZMIX WITH 3% CC AND CIRCULATED TO SURFACE. RAN 1" DOWN BACKSIDE AND PUMPED 40 SX 60/40 POZMIX WITH 3% CC AND CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2968	2972	CSG	
2960	2964	CSG	

INVOICED
JUL 25 2018

Remarks: QES TICKET #54549 115 SX. GEMINI WIRELINE TICKET #1230. DENIED TA

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)