

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-155-21517-00-00
 Spot: NWSESWNW Sec/Twnshp/Rge: 35-22S-10W
2300 feet from N Section Line, 900 feet from W Section Line
 Lease Name: SCHWEIZER Well #: 1-35
 County: RENO Total Vertical Depth: 3720 feet

Operator License No.: 9855
 Op Name: GRAND MESA OPERATING COMPANY
 Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		
PROD	5.5	3710	1680	150 SX
SURF	8.625	260		350 SX
T1	2.875	3620		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2018 12:00 AM
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
 Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA Phone: (620) 617-3357

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
 Date/Time Plugging Completed: 03/22/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3540' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING OFF @ 1680' - PULLED CASING - TTIH TO 1600' PUMPED 12 SXS GEL AND 50 SXS OF COMMON CEMENT WITH 3% CC TAGGED CEMENT @ 1440'. TTIH TO 850' PUMPED 35 SXS COMMON CEMENT WITH 3% . TTIH TO 320' PUMPED 120 SXS COMMON CEMENT WITH 3% CC TO SURFACE. CEMENT FELL BACK 15' - 5 SX TO RAISE TO SURFACE, 3/23/18.

Perfs:

Top	Bot	Thru	Comments
3680	3685		
3652	3658		
3634	3639		
3628	3634		
3614	3624		

INVOICED
 JUL 25 2018

Remarks: QUALITY CEMENTING OUT OF RUSSELL KS, DID CEMENT WORK. LIC. #99998

Plugged through: TBG

District: 02

Signed B. J. Hope
 (TECHNICIAN)

1/24