

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-23484-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 2-26S-18E  
2903 feet from S Section Line, 2824 feet from E Section Line  
Lease Name: ELLIS BROTHERS Well #: 4  
County: ALLEN Total Vertical Depth: 840 feet

Operator License No.: <u>9829</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>HILL OIL AND GAS CO., INC.</u>	PROD	2.875	840		130 SX
Address: <u>PO BOX 2575</u> <u>OLATHE, KS 66063</u>	SURF	5.625	32		40 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2018 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JOE WORKS Company: \_\_\_\_\_ Phone: (620) 473-0520

Proposed Plugging Method: Hook onto 2 7/8", squeeze cement into formation and fill tubing with cement.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/07/2018 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Hooked onto 2.875" casing and pumped 4 bbls of water to establish rate. Pumped cement and cottonseed hulls from top to bottom. Pressured up casing to 800 psi and shut in. A total of 31 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
810	825		

RECEIVED  
KCC DIST # 3  
JUL 25 2018  
CHANUTE, KS

RD

INVOICED

JUL 26 2018

Remarks:

Plugged through: CSG

District: 03

Signed [Signature]  
(TECHNICIAN)