

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 5 TWP. 20 RGE. 11 W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Grant Est ~~1407~~ Box 199

Operator Duke & Wood Address Great Bend, Kans

Field _____ County Barton

Total Depth 3400 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 204' circulated with cement - 5 1/2" at 3322' with
100 sax cement behind.

Filled with chat to 3300', set 4 sax cement with dump bailer,
pulled 2517' 5 1/2", pumped hole full mud using 20 sax

Aquagel, pumped cementing plug to 195', followed by

65 sax cement, filling hole from 195' to 0' with cement.

Mudding and cementing by Sun cementing Co .

PLUGGING
FILE SEC. 5 TWP. 20 R. 11 W
BOOK PAGE 31 LINE 34

Eldon Teets
District Conservation Agent

Date 7-17-52

F