

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-29603-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 19-26S-21E
360 feet from S Section Line, 360 feet from E Section Line
Lease Name: WOLFE Well #: 19-D4
County: ALLEN Total Vertical Depth: 946 feet

Operator License No.: 35018
Op Name: ENTRANSCO ENERGY, LLC
Address: PO BOX 578
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	936		139 SX
SURF	8.625	21		6 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/23/2018 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: RAY GILBERT Company: _____ Phone: (620) 820-9687

Proposed Plugging Method: Run 1" to TD. Cement to surface.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 06/23/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing that was cemented inside the 8 5/8 surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 86 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JUL 27 2018
CHANUTE, KS

RD

INVOICED
JUL 27 2018

Remarks: THIS WELL IS ON A PLUGGING AGREEMENT.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)