

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21069-00-00
Spot: NENENW Sec/Twnshp/Rge: 28-23S-10W
4913 feet from S Section Line, 3126 feet from E Section Line
Lease Name: YUST A Well #: 1
County: RENO Total Vertical Depth: 3949 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3949	1503	175 SX
SURF	8.625	208		150 SX
T1	2.875	3700		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2018 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: KIRK GLENN Company: NOVY OIL & GAS Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/23/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 3750' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING @ 1503' - PULLED CASING TO 1453' SPOTTED 12 SX GEL - THEN 50 SX CLASS A CEMENT W/3% CC. PULLED CASING TO 953' - WAITED 1.5 HOURS - TAGGED PLUG @ 1325' - SPOTTED 35 SX PLUG @ 953'. PULLED CASING TO 288' AND CIRCUALTED TO SURFACE WITH 145 SX CEMENT.

INVOICED
JUL 27 2018

Remarks: COPELAND CEMENTING OUT OF BURRTON - TICKET #47640 - NO LEASE

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

