

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-01491-00-01
Spot: SESESE Sec/Twnshp/Rge: 12-23S-10W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEBER A Well #: 1
County: RENO Total Vertical Depth: 3704 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: 1223 N ROCK ROAD BLDG A STE 200
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3704	2430	150 SX
SURF	8.625	253		185 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/21/2018 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JASON SCHMIDT Company: ZENITH DRILLING CORP Phone: (316) 633-1829

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/23/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3520' WITH 2 SX CEMENT. CUT CASING @ 2430'. PULLED CASING TO 1490' & PLACE CEMENT PLUG WITH 15 SX GEL AND 50 SX COMMON CEMENT. PULL CASING TO 800', WAIT 1.5 HOURS. TAGGED PLUG @ 1100' WITH SANDLINE. SPOTTED CEMENT PLUG @ 800' WITH 35 SX 60/50 POZMIX CEMENT. PULL CASING TO 300' & CIRCULATE TO SURFACE WITH 125 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3599	3609		
3588	3598		
3577	3587		

INVOICED
JUL 27 2018

Remarks: COPELAND CEMENTING OUT OF GREAT BEND - TICKET #46170

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)