

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21869-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 32-29S-8W  
425 feet from S Section Line, 496 feet from W Section Line  
Lease Name: MARX-KINSLER Well #: 3-32  
County: KINGMAN Total Vertical Depth: 4300 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3780		
CIBP		4075		
PROD	4.5	4283	1580	375 SX
SURF	8.625	283		225 SX
T1	2.375	4142		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2018 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: LARRY PRIEST Company: ATLAS OPERATING Phone: (620) 532-9461

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/01/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 2775' AND DUMP 2 SKS CEMENT ON TOP. CUT CASING @ 1580' CAME FREE. PULL CASING TO 1375'. PUMP 12 SX GEL AND 50 SX CEMENT @ 1370'. WAITED 1.5 HOURS, TAGGED PLUG AT 1040'. PULL CASING TO 850' AND PUMP 35 SX. PULL CASING TO 310' AND CIRCULATED TO SURFACE WITH 115 SX.

Perfs:

Top	Bot	Thru	Comments
4157	4176		
3866	3872		
3834	3836		
2839	2844		

INVOICED  
JUL 27 2018

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THE JOB. DENIED TA

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)