

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24013-00-00
Spot: SENENE Sec/Twnshp/Rge: 21-30S-7E
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: LEE Well #: 1
County: COWLEY Total Vertical Depth: 3213 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2800		
PROD	4.5	2932		100 SX
SURF	8.625	201		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2800 WITH 2 SXS. PERF & CIRCULATE 300'-0'. 4 1/2" SQUEEZED FROM 300'-0' ON 9-07-2014

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 07/25/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH SET CIBP @ 2800', DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. RIH W/TUBING @ 420', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 43 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 7-17-18 TAGGED CEMENT PLUG @ 200+ AND 7-22-18 RIH WITH TUBING @ 325'. COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED AND PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TICKET #46426.

Top	Bot	Thru	Comments
2840	2850	CSG	

INVOICED
JUL 27 2018

Remarks: FLUID LEVEL 425'

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)