

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19520-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 17-27S-6E
4984 feet from S Section Line, 2504 feet from E Section Line
Lease Name: MACLEAN Well #: 2
County: BUTLER Total Vertical Depth: 2758 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5	2758		
PROD	5.5	2718		35 SX
SURF	8.625	50		45 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2018 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRANCE CRAWFORD Company: _____ Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 07/18/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 1850-1851, (4 HOLES). RIH W/TUBING @ 1850'. QES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 1789'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250-251' (4 HOLES). RIH W/TUBING @ 260', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 65 SXS CLASS A COMMON TO SURFACE, LAYED DOWN TUBING, SWEDGED INTO 5 1/2" CASING, MIXED & PUMPED 132 SXS CLASS A COMMON 3% CC TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #54477.

Top	Bot	Thru	Comments
2718	2758	OH	


INVOICED
JUL 27 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

