

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21052-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 30-33S-18W
2992 feet from S Section Line, 2285 feet from E Section Line
Lease Name: O DEEWALL Well #: 1
County: COMANCHE Total Vertical Depth: 6100 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5220		WITH 2 SX CMT
PROD	4.5	5534	2680	WITH 120 SX CMT
SURF	8.625	665		WITH 320 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/21/2018 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 5220' WITH 2 SX CMT. PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 350' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2018 12:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 5220' WITH 2 SX CMT. 1ST PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
5270	5350		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

INVOICED

JUL 30 2018

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 27 2018

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JUN 29 2018
KCC DODGE CITY

[Signature]

Form CP-2/3

[Signature]