

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-30006-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 20-27S-20W
702 feet from S Section Line, 640 feet from E Section Line
Lease Name: BRENSING H Well #: 1
County: KIOWA Total Vertical Depth: 5000 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4998	0	WITH 200 SX CMT
SURF	8.625	763		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2018 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY Phone: (620) 617-0603

Proposed Plugging Method: CASING COLLAPSE. RUN TBG TO 2625' & PUMP 30 SX CMT WITH HULLS. PERFORATE AT 1290' & PUMP 50 SX CMT WITH HULLS. PERFORATE AT 790'. CIRCULATE TO SURFACE INSIDE & OUT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2018 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

CASING COLLAPSE. RUN TBG TO 2624' & PUMP 30 SX CMT WITH 150# HULLS-5 SX GEL AHEAD. PERFORATE AT 1290'. PUMP 30 SX CMT WITH 150# HULLS. PERFORATE AT 790'. CIRCULATE CMT TO SURFACE IN & OUT 5 1/2" CASING. PULLED TBG TOPPED OFF WITH 50 SX CMT. 7/3/18: PLUG FELL 250'. TOPPED OFF WITH 50 SX REDI-MIX CMT.

Top	Bot	Thru	Comments
4896	4900		

INVOICED
JUL 30 2018

Remarks: USED COMMON CEMENT BY QUALITY WELL.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

RECEIVED
JUL - 5 2018
KCC DODGE CITY

JUL 27 2018
CONSERVATION DIVISION
WICHITA, KS

Kms