

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23816-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 20-25S-12W
4943 feet from S Section Line, 408 feet from E Section Line
Lease Name: FRITZEMEIER Well #: 1
County: STAFFORD Total Vertical Depth: 4240 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3570		WITH 2 SX CMT
PROD	5.5	4237	2210	WITH 180 SX CMT
SURF	8.625	715		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2018 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3570' WITH 2 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2018 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 3570' WITH 2 SX CMT. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3983	3990		
3732	3736		
3611	3615		

INVOICED
JUL 30 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01


Signed: 

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 27 2018

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JUL 19 2018
KCC DODGE CITY 

Form CP-2/3

KMS