

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-057-20993-00-00  
 Spot: NENENE Sec/Twnshp/Rge: 34-29S-22W  
5071 feet from S Section Line, 335 feet from E Section Line  
 Lease Name: KREGAR Well #: 1-34  
 County: FORD Total Vertical Depth: 5450 feet

Operator License No.: 31822  
 Op Name: JOLEN OPERATING COMPANY  
 Address: 100 N BROADWAY AVE STE 2460  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5250		WITH 2 SX CMT
PROD	4.5	5438	2200	WITH 175 SX CMT
SURF	8.625	354		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2018 8:00 AM  
 Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
 Proposal Revd. from: DENNIS POPE Company: JOLEN OPERATING Phone: (405) 235-8444

Proposed Plugging Method: CIBP 10 SX Cement @ 5250', Cut & pull free pipe 1410' 5sx cement 390' with 50 sx cmt 40' with 20 sx cmt

Plugging Proposal Received By: LARRY HARRIS Witness Type: PARTIAL  
 Date/Time Plugging Completed: 06/27/2018 2:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5250' WITH 2 SX CMT. 1ST PLUG AT 1410' WITH 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:			
Top	Bot	Thru	Comments
5283	5328		
INVOICED JUL 30 2018			

Remarks: USED CLASS C CEMENT BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED  
 JUN 29 2018  
 KCC DODGE CITY

RECEIVED  
 KANSAS CORPORATION COMMISSION

JUL 27 2018

CONSERVATION DIVISION  
 WICHITA, KS

Form CP-2/3

KMS