

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20756-00-01
Spot: NWSESW Sec/Twnshp/Rge: 29-29S-11W
990 feet from S Section Line, 3646 feet from E Section Line
Lease Name: BLACKWELDER Well #: 1
County: PRATT Total Vertical Depth: 3990 feet

Operator License No.: 31434
Op Name: L & J OIL PROPERTIES, INC.
Address: 1700 N WATERFRONT PKWY BLDG 30
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2700		WITH 2 SX CMT
CIBP		3800		WITH 2 SX CMT
PROD	4.5	3889	0	WITH 250 SX CMT
SURF	8.625	320		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/26/2018 9:30 AM
Plug Co. License No.: 35456 Plug Co. Name: 4G WELL SERVICE LLC
Proposal Rcvd. from: KEITH BRIGHT Company: L&J OIL PROPERTIES Phone: (316) 239-8593

Proposed Plugging Method: SET CIBP @ 3800' WITH 2 SX CMT. SET CIBP @ 2700' WITH 2 SX CMT. PERFORATE AT 780'. PUMP 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 350' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2018 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S AT 3800' & 2700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PRESSURE TEST 4 1/2" CASING. HELD. PERFORATE AT 750' & PUMP 50 SX CMT (25 SX OUT PERFS & 200# HULLS & 25 SX CMT INSIDE 4 1/2" CASING). PERFORATE @ 350' & CIRCULATE CMT TO SURFACE INSIDE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH 180 SX CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3839	3894		
2744	2776		

INVOICED
JUL 30 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
JUN 29 2018
KCC DODGE CITY

JUL 27 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS