

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20623-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 10-34S-11E
2901 feet from S Section Line, 3744 feet from E Section Line
Lease Name: FADLEY Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1259 feet

Operator License No.: 34680
Op Name: TDOT OIL, INC.
Address: PO BOX 117
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
PROD	4.5	1259		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TIM DOTY Company: _____ Phone: (620) 331-9791

Proposed Plugging Method: Cemented to top, but no cement tickets. Plug according to KCC instructions.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 06/28/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1200' gelled hole spotted 5 sack plug. Pulled 1" and perforated casing at 750' and 350'. Ran 1" back to 750' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 90 sacks of cement with 3% gell were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1146	1166		

RECEIVED
KCC DIST # 3
AUG 01 2018
CHANUTE, KS

DS

INVOICED

AUG 02 2018


INVOICED
AUG 02 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)